

"AMRELI JILLA PRATHMIK SHIKSAKONI SARAFI SAHAKARI MANDALI." AMRELI

DIST.- AMRELI

NAME OF SCHEME :- SELF FUND

**NAME OF WORK:- FURNITURE WORK OF NEW BUILDING OF AMRELI JILLA PRATHMIK SHIKSAKONI SARAFI
SAHAKARI MANDALI." AMRELI**

LOCATION : AMRELI

SCHEDULE - B

I. No.	Item Description	Qty.	Rate	Per	Amount
1	TABLE : Providing and fixing in position table of various size as per architect drawing incl. side storage by using 18mm thick plywood for top and all other horizontal and vertical members. In top around all side with 50mm wide 12mm thick plywood for making groove all exposed surface of table excluding top are 1mm thick approved and selected laminate finished. All drawer making from 18mm thick side and 8mm thick bottom plywood with all side 1mm thick white laminate and front side 1mm thick selected laminate with telescopic channel with Indian teakwood J-Type handle with lock. Key board tray making from 18mm thick plywood with three side vertical 40mm facia and front side top 20mm wide 5mm thick round edge teakwood batten patti with bothside telescopic channel. all other design making from plywood and laminate finished as per detail drawing and directed by Engineer-in-charge. all materials using as per approval of the project consultant. all necessary hardware and fitting in stainless steel finished, Incl. All type of materials and labour charges etc. comp.				
	Approved Company				
	Ply wood : Kitply, Greenply, Greenpeel National or equivalent				
	Laminate :Royale Touch, Sunmica, Formica, Greenlam, Durian, Silicon, Merino				
	Hardware Materials : Godrej, Polo, Uropa and Ozone				
		7.00	25250.00	Cumt.	176750.00

I. No.	Item Description	Qty.	Rate	Per	Amount
2	BOARD ROOM TABLE : Providing and fixing in position table of various size as per architect drawing using 18mm thick plywood for top boarder facia 40mm thick and all other horizontal and vertical members. all exposed surface of table are 1mm thick approved and selected laminate finished. all other design making from plywood and laminate finished as per detail drawing and directed by Engineer-in-charge. all materials using as per approval of the project consultant. all necessary hardware and fitting in stainless steel finished, Incl. All type of materials and labour charges etc. comp.				
	Approved Company				
	Ply wood : Kitply, Greenply, Greenpeel National or equivalent				
	Laminate : Sunmica, Formica, Greenlam, Timex, Durian, Silicon, Merino and Royale Touch or equivalent				
	Hardware Materials : Godrej, Polo, Uropa and Ozone				
		1.70	20200.00	Cumt.	34340.00
3	BACK SIDE FILE RACK : Providing and fixing in position back side File Rack of various size as per Architect drawing by using 18mm thick plywood for top and bottom, 12mm thick plywood back side and 18mm vertical partition and horizontal self, and front door. All inner side exposed by 1mm thick white laminate and outer side 1mm thick selected laminate finished. All drawer making from 18mm thick side and 8mm thick bottom plywood with all side 1mm thick white laminate and front side 1mm thick selected laminate with telescopic channel with Indian teakwood J-Type handle with lock. all necessary hardware and fitting in stainless steel finished, Incl. All type of Materials and Labour Charges etc. comp as per drawing and directed by Engineer-in-charge.				
	Approved Company				
	Ply wood : Kitply, Greenply, Greenpeel National or equivalent				
	Laminate : Sunmica, Formica, Greenlam, Timex, Durian, Silicon, Merino and Royale Touch or equivalent				
	Hardware Materials : Godrej, Polo, Uropa and Ozone				
		15.50	55550.00	Cumt.	861025.00

I. No.	Item Description	Qty.	Rate	Per	Amount
4	FULL HEIGHT PARTITION : Providing and fixing of full height Partition with Partially 12mm thick toughened glass as per drawing with 40mm thick made from 12mm thick both side plywood with hollow type including all exposed surface with 1mm selected laminate. Door making of 12mm toughened glass with all accessories like floor spring, patch, lock, 30mm dia 600mm long twin handle etc. are Ozone make as per manufacturers specification and as per the drawings and also directed by Architects / Consultant. all the material will be approved by Architect / Project consultant in charge.				
	Approved Company :				
	Glass : Modiguard, Saintgobine				
	Ply wood : Kitply, Greenply, Greenpeel National or equivalent				
	Laminate : Sunmica, Formica, Greenlam, Timex, Durian, Silicon, Merino and Royale Touch or equivalent				
	Hardware Materials : Godrej, Polo, Uropa and Ozone				
		96.10	9090.00	Sqmt.	873549.00
5	CEILING BOX : Providing and Fixing ceiling box for AC indoor unit making from 18mm thick plywood with ceiling support including all exposed surface with 1mm thick selected laminate. All the work shall be carried out as per the instruction and drawings supplied by the Consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
	Approved Company :				
	Ply wood : Kitply, Century, Greenply, National, Sarda, Mayur and Silicon				
	Laminate : Sunmica, Formica, Greenlam, Timex, Durian, Silicon, Merino and Royale Touch or equivalent				
		1.00	22725.00	Cumt.	22725.00
6	Wall Panneling : Providing and Fixing wall panelling from 12mm thick plywood with all exposed surface by 1mm thick selected laminate or mirror. All the work shall be carried out as per the instruction and drawings supplied by the Consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
	Approved Company :				
	Ply wood : Kitply, Century, Greenply, National, Sarda, Mayur and Silicon				
	Laminate : Sunmica, Formica, Greenlam, Timex, Durian, Silicon, Merino and Royale Touch or equivalent				
		41.10	3535.00	Sqmt.	145288.50

I. No.	Item Description	Qty.	Rate	Per	Amount
7	Frosted Glass Film : Providing and pesting frosted film on Glass as per design given by Engineer-in-charge. The work completed with all materials and labour and finishing completed as per directed by Engineer-in-Charge.				
	Approved Company - GM				
		2.80	1262.50	Sqmt.	3535.00
8	Shelf : Providing and fixing shelf as per Architect drawing by using 18mm thick plywood with facia 18mm groove make from 50mm wide 18mm thick plywood with all border and middle support with facia 1mm thick selected laminate finished. All the work shall be carried out as per the instruction and drawings supplied by the Consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
	Approved Company :				
	Ply wood : Kitply, Century, Greenply, National, Sarda, Mayur and Silicon				
	Laminate : Sunmica, Formica, Greenlam, Timex, Durian, Silicon, Merino and Century				
		1.30	5555.00	Sqmt.	7221.50
9	ARTIFICIAL GLASS WHITE : Providing and fixing 15mm thick artificial glass white stone with necessary cutting including cutting cable manager as per drawing, all exposed edge with mirror polishing and fixing with silicon. All the work shall be carried out as per the instruction and drawings supplied by the Consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
		12.20	7070.00	Sqmt.	86254.00
10	Loft Furniture : Providing and fixing loft furniture making from 18mm thick plywood framing and shutter including horizontal and vertical members, all exposed surface with 1mm thick selected laminate finished and inner side 1mm thick white laminate including all accessories like handle, hinges, etc. complete. All the work shall be carried out as per the instruction and drawings supplied by the Consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
		10.20	6060.00	Sqmt.	61812.00

I. No.	Item Description	Qty.	Rate	Per	Amount
11	KITCHEN PLATFORM : The frame work of the cabinets including drawer fascia, sides, bottom, shelves etc. shall be made out of 18mm thick Marine plywood Shutters shall be made out of 18mm thick Marine plywood. Each shutter shall be fixed to the framework using two numbers of best quality EURO type Slip/Auto Hinges and provided with one approved quality and profile brush finished Stainless Steel (SS) handle of grade 304.				
	Each drawer fascia shall be made out of 18mm thick Marine plywood with inner side white laminate and all exposed with selected laminate of approved quality and make SS 304 grade baskets / accessories shall be mounted on approved quality, high precision telescopic channels/slides to be designed as per drawer size and to meet the weight requirement with minimum length of 500mm to ensure smooth movements of drawer with /without content weights and provided with approved quality SS handles of grade 304. The telescopic channel rails may be provided as per specifications.				
	In each kitchen there should be a minimum of 1 No. cup & saucer basket (4" size), 1 No. Glass basket (6" size), 2 No. 'Thali' basket (8" size), 1 No. Perforated Cutlery basket (4" size), 1 Nos of plain multipurpose baskets (4" size), 2 Nos of plain multipurpose baskets (6" size), 1 Nos of plain multipurpose baskets (8" size), 1 No. shutters below the sink. 1 No plain shutter at the gas cylinder. The shutters shall be of 18mm Marine plywood fascia, sides, bottom as required as per the drawings given.				
	All the stainless steel baskets shall be of maximum size which can be accommodated in the respective space available inside each cabinets for smooth functioning of railing. The Stainless Steel rods provided in the baskets shall be of combination of rods and the spacing of these various steel rods as per directed by Engineer-in-charge.				
	All shelves shall be supported on approved quality Stainless Steel (SS) pins and shall be adjustable for various height requirements. The unit shall be firmly fixed to the walls/ slabs/ floor using non-corrosive metal screws of appropriate size and rawl plugs. All exposed surfaces and internal surfaces of the units shall have machine pressed lamination having thickness 1mm and 0.8mm respectively of approved shade and make (Merino, Greenlam or approved equivalent) and pasted with synthetic resin based adhesive (Fevicol, Vamicol or approved equivalent) etc.				
	All faces and edges of support slabs below the kitchen slab, wooden planks for supporting telescopic channel rails.				

I. No.	Item Description	Qty.	Rate	Per	Amount
	Payment shall be made on the basis of front elevation area of modular units only. It is clarified that sides, top and bottom surfaces will not be measured for payment.				
	The wooden frame for shutter shall be made of minimum 70 mm wide marine plywood with lamination, wherever required. The telescopic channel shall be supported with 75 mm wide vertical and horizontal marine plywood members with laminate fixed on vertical support. If there is a need of erecting additional vertical marine plywood members with laminate on account of site conditions, the quoted rate shall have provision of carrying out these works.				
	All necessary hardwares, wooden members with required thickness for fixing telescopic channel rails and filling the gaps shall be included in the quoted rate. The quoted rate shall include making of vertical partition below the existing kitchen slab with 18mm thick marine plywood if necessary to accommodate modular kitchen units as per the requirement.				
	Approved Company				
	Ply wood : Kitply, Greenply, National, Sarda, Mayur and Silicon				
	Laminate : Sunmica, Formica, Greenlam, Durian, Silicon, Merino, Royale Touche				
	Hardware Materials : Godrej, Polo, Uropa and Ozone				
		1.37	23230.00	Sqmt.	31825.10

I. No.	Item Description	Qty.	Rate	Per	Amount
12	CHAIR (LOW BACK) Providing and supplying Visitor Chair Low Back shall be made with Polyurethane moulded cushion of average density range between 45.50 Kgs/Cumt. giving contoured raised profile pattern on seat and back for comfort. The seat shall be supported on plywood and shall be covered with fabric of colour and design as approved by the Architect / Consultant. The back shall be snapfit and shall be covered by an impact resistance plastic moulded cover with ribbed pattern having polyurethane of +/- 5 mm having center tilt & gas Mechanism. Armrests shall be made of self skinning polyurethane with metal insert and shall have arrangements at the bottom to fasten to the seat by the means of bolts. Five pronged injection moulded base shall be made out of glass filled nylon and shall be fitted with twin wheel castor. All the work shall be carried out as per the instruction and drawings supplied by the consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge. All type of Materials and Labour Charges etc. comp.				
		42.00	4545.00	No.	190890.00
13	PLASTIC MOULDED CHAIR : Supplying of Plastic durable moulded plastic chair having Length 51cm, Width 58cm and height 79cm (tolerance +25mm) of approved brand round design as per approved by Architect / Project consultant in charge.				
		12.00	1767.50	No.	21210.00
14	HIGH BACK CHAIRS : Providing and fixing High Back chairs made of 1" ERW pipe of 16 gauge seat and back is made of 12mm hot press single ply and provided with 40/50 & 23 density 12mm pure foam (Feather foam make) and covered with premium quality of leather/fabric. The chair with duo colour fabric combinations as per EIC / Architect. The chair shall be provided with 120mm BIFMA Passed gas lift and conventional tilt mechanism with one lever control for lock and seat height adjustment. Plate thickness shall 2.5 mm and angle is 3~18 (BIFM Passed) with poly urethane one pipe handle and nylon base having 1359 kg weight capacity as per BIFM standard. all the metal parts of the chair are pre treated prior to powder coating/ chrome. size 675 x 675 x 1165mm. seat ht: 440/540mm.				
		5.00	17675.00	No.	88375.00

I. No.	Item Description	Qty.	Rate	Per	Amount
15	DOOR SHUTTER : Providing and fixing 38mm thick shutters for Doors, made from 35mm thick flush door of double core, waterproof and anti-termite with bothside 1mm thick selected laminate with all edge 10mm thick indian teack wood bidding and making groove as per drawing. all accessories like SS hingies, door stopper, latch, concealed lock etc. as per approved by Architect/Engineer in charge.				
		18.30	8585.00	No.	157105.50
16	AIR CONDITIONER Supplying and installation of 1.1 Ton, 2 Star Non Inverter Split Air conditioner with nominal capacity having Cooling capacity W-3600, Rated Power Input : 868W, Rated Current : 3.85A, ISSER : 5.10, Voltage : 230V /50Hz/Single Phase, Air Flow rate : 545-820 CMH, Noise level Indoor Unit : 43-50 db, Outdoor Unit : 60 db, Function modes : Auto/ Cool/ Fan/ Dry-shall have sleep and power saving mode, Other Features : Automated vertical swing for horizontal louvers, Antifreeze thermostat, Compressor : Rotary type, Body surface finish : Powder coated high quality paint finish, Air filtering unit : Activated carbon cartridge, dust proof and anti bacterial filter, Length of tubings : as per the installation requirement, Remote handset : LCD display with night glow etc will be approved by Architect / Project consultant in charge.				
	Approved Company				
	Mitshubishi, Hitachi				
	1.1 TR CAPACITY				
		1.00	53530.00	No.	53530.00
17	AIR CONDITIONER Supplying and installation of 2.2 Ton, 3 Star Non Inverter Split Air conditioner with nominal capacity having Cooling capacity W-7700, Rated Power Input : 1800-2050W, Rated Current : 7.08A, ISSER : 5.10, Voltage : 230V /50Hz/Single Phase, Air Flow rate : 980-1400 CMH, Noise level Indoor Unit : 46-54 db, Outdoor Unit : 60 db, Function modes : Auto/ Cool/ Fan/ Dry-shall have sleep and power saving mode, Other Features : Automated vertical swing for horizontal louvers, Antifreeze thermostat, Compressor : Rotary type, Body surface finish : Powder coated high quality paint finish, Air filtering unit : Activated carbon cartridge, dust proof and anti bacterial filter, Length of tubings : as per the installation requirement, Remote handset : LCD display with night glow etc will be approved by Architect / Project consultant in charge.				
	Approved Company				

I. No.	Item Description	Qty.	Rate	Per	Amount
	Mitshubishi, Hitachi				
	2.2 TR CAPACITY				
		1.00	90900.00	No.	90900.00
18	CASSETTE AIR CONDITIONER Supplying and Installation in Position 3 Star Rating cassette A/C of various capacity for office building, Nominal Capacity : 7620W, Cooling capacity : 5.25+/- 2%, Electricity input : 230V /50Hz/Single Phase, Coefficient performance : 3 (Minimum), Max.Ambient temperature : 48° C +/- 5%, Moisture removal rate : 2 +/- 10% liter/hour, Air Flow rate : 5.6 cmm (Minimum), Noise level , Indoor Unit : Less than 45 db, Outdoor Unit : Less than 55 db, Function modes : Auto/Cool/Fan/Dry-shall have sleep and power saving mode, Other Features : Automated vertical swing for horizontal louvers, Antifreeze thermostat, Compressor : Rotary type, Body surface finish : Powder coated high quality paint finish, Air filtering unit : Activated carbon cartridge, dust proof and anti bacterial filter, Length of tubings as per the installation requirement, Remote handset : LCD display with night glow, Voltage Stabilizer : Stabilizer having ISI Quality certification and power rating that matches with the power rating of the A/C unit, All the work shall be carried out as per the instruction and drawings supplied by the consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
	Approved Company				
	Mitshubishi, Dikin				
	2.00 TR Capacity 4 Way Cassette AC				
		2.00	131300.00	No.	262600.00

I. No.	Item Description	Qty.	Rate	Per	Amount
19	LED T.V. Supplying and Installation QLED 4K Smart TV, Resolution : 4K (3840 x 2160), Picture Engine : Quantum Processor Lite 4K, Quantum HDR, Dual LED Contrast, Motion Xcelerator, 20W Sound Output, Speaker Type 2CH, Built-in-Alexa Voice Assistant, Connectivity HDMI - 3, USB : 2 x USB-A, Ethernet - 1, Wi-Fi, Bluetooth, Digital Audio Out, Cabinet Accessories : Remot control with batteries, Connecting Laptop, Versatile 2-5 feet extension range for a variety of viewing angles Hanging telescoping Stand fixing with fastner Heavy-duty construction with a weight capacity of not less than 65 kg & All required accessories for wall mounting, All the work shall be carried out as per the instruction and drawings supplied by the consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
	Approved Company				
	Samsung				
	Size : 1.63m (65")				
		1.00	141400.00	No.	141400.00
20	LED T.V. Supplying and Installation QLED 4K Smart TV, Resolution : 4K (3840 x 2160), Picture Engine : Quantum Processor Lite 4K, Quantum HDR, Dual LED Contrast, Motion Xcelerator, 20W Sound Output, Speaker Type 2CH, Built-in-Alexa Voice Assistant, Connectivity HDMI - 3, USB : 2 x USB-A, Ethernet - 1, Wi-Fi, Bluetooth, Digital Audio Out, Cabinet Accessories : Remot control with batteries, Connecting Laptop, Versatile 2-5 feet extension range for a variety of viewing angles Hanging telescoping Stand fixing with fastner Heavy-duty construction with a weight capacity of not less than 65 kg & All required accessories for wall mounting, All the work shall be carried out as per the instruction and drawings supplied by the consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
	Samsung				
	Size : 2.14m (85")				
		1.00	232300.00	No.	232300.00

I. No.	Item Description	Qty.	Rate	Per	Amount
21	REVERSE OSMOSIS : A 25 LPH (Liters per Hour) RO+TDS system typically purifies water using reverse osmosis and a TDS (Total Dissolved Solids) controller, with features like multi-stage filtration, UV sterilization, and a capacity to handle up to 2000 ppm TDS, Purification Capacity: 25 Liters per hour, Filtration Stages: Multi-stage purification, including RO (Reverse Osmosis), UV (Ultraviolet) sterilization, and sometimes UF (Ultrafiltration) TDS Handling : Designed to handle input water with Total Dissolved Solids (TDS) levels up to 2000 ppm, TDS Adjustment: Includes a TDS controller to adjust the TDS level of the purified water, Materials: Typically uses food-grade stainless steel and ABS plastic for durability and safety, UV Lamp: UV LED 24v, Power Consumption: 230 V AC to 24 V DC 2.5 AMP, Installation: Can be wall-mounted or countertop, Rejection of TDS: Up to 95%, Recovery: Up to 25%, Input water Temperature: Min 5 Celsius & Max 50 Celsius, Total Hardness: 500 ppm (max), Suitable for TDS Levels: 2000, Purification Method: RO+UV+Alkaline, Ultra violet lamp power rating: 11 W etc. Complete as per approved and directed by project architect.				
		1.00	18685.00	No.	18685.00
22	WATER HEATER (GEYSER) : Providing, supplying and installation of instant water heater (Geyser) of 3 litre capacity with feroglass Technology heavy duty heating element, Anode Rod, Colour Changing LED Indicator, 0.8 MPa high working pressure, Whirl flow technology, Wattage 3000 watt, Rated Voltage 230V, Single phase, 50 Hz, AC, etc. Complete as per approved and directed by project architect.				
		1.00	4040.00	No.	4040.00

I. No.	Item Description	Qty.	Rate	Per	Amount
23	COT & MATTRESS Cot -Provide and fix Cot of size (1) 1980 x 800 x 450mm from 12mm thick ply base for the bed including necessary framing, with 19mm ply with exposed face 1mm thick as per drawings and directed by project Architect. Mattress: size 1980 x 800 x 150 with Sandwich construction round corners, hitlon thickness 60mm and hitlon density 23 GM/dcm cube. Coir both side thickness 20mm, density 70 GM/dcm cube., Quilting combination layer with piled foam quilting one side with thickness of 14mm, piled foam density 18GM/dcm cube. PU foam/EPE sheet side walling thickness 3mm , total thcikness of mattress to be 114mm with Fabric 85 GSM, fabric poly cotton with maroon with Pearl gold print fabric of approved make with bed spread and pillows, complete as per the dwg and the instructions of the Architects/Consultant. All the work shall be carried out as per the instruction and drawings supplied by the Consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
		2.00	30300.00	No.	60600.00
24	GYPSUM CEILING Providing and Fixing in position false ceiling in gypboard 12 mm thick for horizontal and vertical fixed over. G.I.framework as specified by india Gypsum co. ltd. incl. trap doors for A.C. and Lights as per Architect Design and Drawings. Sheet and other material like "L" Patty (24 Gauge), Bottom Patty (24 Gauge), Screw and Fastner shall be using a Gyproc (Saint Gobine Company) incl. All type of Materials and Labour Charges etc. comp.				
		165.00	1212.00	Sqmt.	199980.00

I. No.	Item Description	Qty.	Rate	Per	Amount
25	METAL CEILINGS WITH XL 24MM GRID Providing and fixing in true horizontal level 600 mm. X 600 mm. false ceiling system manufactured by M/s. Armstrong World Industries using hot dipped galvanized steel section, exposed surface with pre-coated capping, main tee of size 24 x 32 mm., having 0.27 mm gauge at every 1200 mm. centre to centre maximum and rotary stitched cross tee of size 24 x 27 mm, having 0.27 mm gauge at every 600 mm. c/c. and sub cross tee of size 24 x 27 mm, having 0.25 mm gauge at 1200 mm c/c. and wall angle of size 19 x 19 mm., having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 1200mm c/c. in both directions using 2.0 mm. thick pre-straightened GI wire laying FINE FISSURED BUTT Edge ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.55, Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/m0K, Humidity Resistance of 99% , having Fire Performance CLASS O / CLASS 1 (BS 476), surface having 3 coats of white paint with Fine Fissured, back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete. All type of Materials and Labour Charges etc. comp.				
		38.30	1363.50	Sqmt.	52222.05
26	WPC Ceiling "Providing and fixing WPC (Wood-Plastic Composite) false ceiling panels of approved shade and design. Panels shall be of size [e.g., 2950mm x 195mm x 27mm] with a minimum wall thickness of [e.g., 5mm]. The installation includes a supporting framework of GI/Aluminium sections (30mm x 20mm or as per site condition) fixed to the existing soffit at [e.g., 450mm] intervals using expansion fasteners. The item includes all necessary clips, screws, edge trims, and scaffolding. Work must be finished as per manufacturer's specifications and as directed by the Engineer-in-Charge."				
		17.80	2575.50	Sqmt.	45843.90

I. No.	Item Description	Qty.	Rate	Per	Amount
27	ROLLAR BLIND Providing and Fixing in Position 2000 mm wide black out ROLLER BLINDS of fabric 100% polyester (Plain Weave), with pigment PVA-coating on both side of the fabric with one intermediate black coating of Dupont make, flame retardant, of Technofab make as approved with regular imported spring type one touch mechanism and include all standard fittings, accessories as per the manufacturer's specification, for windows as directed, The Rate shall be included all materials, hardware and labour etc. All the work shall be carried out as per the instruction and drawings supplied by the consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
		33.90	3535.00	Sqmt.	119836.50
28	Supplying and Installation in Position Ceiling Fan Crompton make Model Name : HS plus (High Speed Plus) Input Power : 53 watts, Down Rod : 450 mm, Regulator : as per company make, Air Delivery : 218 Cumt / Min, RPM : 370, Ball bearing-2, Leaf-3, Service value : 4.11, Colour : White, Size : 1200 mm , All the work shall be carried out as per the instruction and drawings supplied by the consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge. (M.Rate)				
		17.00	2525.00	Piece	42925.00
29	NAME PLATE Providing and fixing signage with 2mm thk SS brush finished plate with etching names fixed on the door with Birla 3M double sided sticker as per the approved sample. All the work shall be carried out as per the instruction and drawings supplied by the Consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
		0.50	48480.00	Sqmt.	24240.00

I. No.	Item Description	Qty.	Rate	Per	Amount
30	Granite Takti "Providing and fixing of polished Granite Stone Takti (Name Plate/Inaugural Plaque) of size [e.g., 1200mm x 910mm x 18mm] of approved color and shade (Jet Black/Ruby Red). The work includes precise computerized laser engraving or deep sandblast etching of text/logos as per the provided design. The plate shall be fixed to the wall or pedestal using high-strength epoxy adhesive or stainless steel (SS 304) decorative stud bolts with spacers. The item includes fine edge polishing, chamfering of corners, all lead, lift, tools, and labor. Final finish shall be as per the satisfaction of the Engineer-in-Charge."				
		1.10	15150.00	Sqmt.	16665.00
31	EPABX Supplying, erecting, commissioning and testing analog EPABX CMOS microprocessor based system having common features With remote programming & remote dialing having following other common features. Auto Call Disconnect- (Incoming - Local- STD) with programmable timing- External Call forward with DOSA- Walk in Class of service & trunk reservation- Boss ring & call back on No Reply last caller recall CLI- Hot Line with Delay & with No.- Unsupervised Conference- Serial DISA (DISA with option to dial another No. if Extn. is No Reply)- Programming Flexibility of all features related to timer (41 Timer)-10 Different group of out going call restriction like 95, 97, 98 etc. Having 4 incoming junction line & 12 extensions.				
		1.00	35350.00	No.	35350.00
32	TELEPHONE : Supplying, and instalation Caller ID Landline, DTMF/FSK Compatible, 16 Digit LCD, Two Way Speaker phone, Music On Hold, In-use LED, 8 One Touch Memories, 30 Incoming/15 Outgoing calls Memory, 16 Ring Melodies of approved brand.				
		7.00	1767.50	No.	12372.50
33	TELEPHONE WIRING : Supplying and instalation of Telephone wiring all with two pair cable as per plan and directed by project architect. All wiring concealed in existing pipe upto connected with EPBX as per requirement with jack and junction box. All the work carried out as per directed by project architect.				
		1.00	15150.00	Job	15150.00

I. No.	Item Description	Qty.	Rate	Per	Amount
34	CCTV Servailance System : Supplying and instalation of CCTV servailance system having 28 No. Bullet/Dom 4MP camera as per drawing, 32 channel NVR with rack of - 4 SATA - 256 MBPS, 2 nos of 2 TB Hardisk necessary POE, with box, Cat-6 cable as per require with piping, RJ45 jack and necessary socket box, etc. complete with all types of materials and labour work complete as per drawing and as per directed by project architect.				
	Approved Company : Hikvision				
		1.00	328250.00	Job	328250.00
35	LANE CABLE : Providing, Supplying and instalation of Lane Cable Cat-6 including necessary piping and RJ-45 crimping, RJ-45 socket with box, plate etc. complete of entire building as per drawing and directed by architect.				
		1.00	25250.00	Job	25250.00
36	UPS : Providing, Supplying and instalation Luminous Optimus 6000 Sine wave UPS having 5 KVA, 48V DC with 4 nos. Liminous tall tubular battery of 12V 250AH UCTT28066 with 5 year battery warranty including battery stand and complete instalation with necessary switch board.				
		1.00	128270.00	Set	128270.00
37	LED LIGHT Supplying and Erecting CRCA / Die cast aliminium poweder coated LED panel light, 200 x 200 mm Size of premium range panel front frame with translucent cover, All the work shall be carried out as per the instruction and drawings supplied by the consultant and the time of execution of works. Material will be approved by Architect / Project consultant in charge.				
	(A) 18 Watt				
		61.00	757.50	No.	46207.50
	(B) 12 Watt				
		16.00	681.75	No.	10908.00
	(C) 9 Watt				
		13.00	434.30	No.	5645.90
	(D) 9 Watt C.O.B.				
		5.00	1565.50	No.	7827.50
	(E) 12 Watt C.O.B.				
		6.00	1717.00	No.	10302.00
	(F) 20 Watt 20 Watt LED Batten Tube Light, 100 Lumens Per Watt, 6500K, Long Life, Anti-glare Diffuser, Fluctuation Proof				
		4.00	252.50	No.	1010.00
	(G) 17x6mm Surface Aluminium Profile Light Channel with White Diffuser with LED Strip Light including all accessories				
		42.40	1565.50	Rmt.	66377.20

I. No.	Item Description	Qty.	Rate	Per	Amount
	(H) Elevation Light Fixture On Elevation "Supply, Installation, Testing, and Commissioning (SITC) of exterior grade, architectural LED elevation light fixtures (Make: [Approved Manufacturer Name, e.g., Philips, Osram,Wipro, etc.], Model: [Specific Model Number]) for building facade/elevation as per the Architectural/Electrical consultant's design and drawings. The scope includes providing all standard accessories such as an integral electronic driver, mounting brackets/arrangements, glands, necessary IP65/IP66 junction boxes, and all required hardware (SS nuts, bolts, etc.). The fixture shall have a die-cast aluminium housing with a powder-coated finish, tempered/toughened glass lens, an IP rating of IP65 or better, a minimum power factor of 0.95, and a high Color Rendering Index (CRI >80). The item covers all wiring from the nearest Lighting Distribution Board (LDB) using FRLS PVC insulated copper conductor cables of appropriate size laid in 20/25mm dia PVC rigid conduits, scaffolding, all lead, lifts, and labour to achieve the final desired lighting effect as directed by the Engineer-in-Charge."				
		8.00	1767.50	Nos.	14140.00
	(I) 1 Watt LED Spotlight "Supply, installation, testing, and commissioning (SITC) of recessed-type/surface-mounted miniature 1 Watt LED spot light fixtures (Make: [Approved Manufacturer Name, e.g., Osram, Philips, Wipro, etc.], Model: [Specific Model Number]) for architectural accent lighting as per reflected ceiling plans and electrical drawings. The fixture shall have a die-cast aluminium/thermoplastic body, finished in [e.g., White, Silver, Black powder coat], fitted with a clear/frosted lens. It must include an integrated or remote constant current driver with necessary wiring up to the nearest Junction Box (JB) or Lighting Distribution Board (LDB) using FRLS PVC insulated copper conductor cables of appropriate size laid in PVC conduit. The item covers all required cutout sizes ([e.g., 30mm/50mm dia]), mounting clips/brackets, scaffolding, all lead, lifts, labor, and final alignment/commissioning to achieve the desired lighting effect as directed by the Engineer-in-Charge."				
		20.00	505.00	No.	10100.00

I. No.	Item Description	Qty.	Rate	Per	Amount
38	LED SOLAR LIGHT : Supplying and Installation of Approved make Integrated LED Solar light fitting comprising in built Poly crystalline solar panel, Lithium-ion 3.7 V battery, LED CRI Greater than 70, CCT-6500K, 80 lum/watt all housed in Extruded Aluminium body, with motion sensor & auto on -off device erected with suitable wall bracket 18 watt LED light, with 22 W Solar panel, 3.7 V 39500 to 40500 mAh battery, 1250-1350 lm luminous flux, suitable for mount on 3.5 to 4 mtr height pole.				
		4	3535.00	No.	14140.00
39	BATH ACCESSORIES TOWEL RACK: Providing, supplying and fixing Stainless Steel 304 Grade Folding Towel Rack as per approved by project consultant.				
		2.00	2222.00	No.	4444.00
40	BATH ACCESSORIES SOAP DISH WITH TUMBLE HOLDER: Providing, supplying and fixing Stainless Steel 304 Grade Soap dish with tumbler holder as per approved by project consultant.				
		2.00	959.50	No.	1919.00
41	Providing and fixing liquid soap dispenser and wall mountable comes in a standard size of 15*11*5.5 and weight 600 Grams. This is 304 stainless steel and glass soap dispenser with stand Anti-Rust & Corrosion-Proof. Equipped with an elegant frosted glass liquid bottle and chrome finish stand				
		2.00	1363.50	No.	2727.00
42	Mirror : Providing and fixing mirror with dimond edge polished fixing with SS stud as per directed by Engineer in charge.				
		3.60	1515.00	Sqmt.	5454.00
43	Dust Bin : Supplying dust bin of Stainless Steel anti-fingerprint and anti-rust coating, Paddle Operating Cover, Size : 10" Dia, 15" Height, with Removable inner liner with a stainless steel carrying handle lifts out for easy disposing of garbage without using plastic bags and easy cleaning the whole small garbage can. Material supply will be prior approval from the Architect / Project consultant.				
		16.00	1818.00	No.	29088.00

I. No.	Item Description	Qty.	Rate	Per	Amount
44	Fabrication Grill "Supply and Installation of exterior-grade, architectural Jali (screen/grille) fabricated from CNC-cut MS (Mild Steel) plate of specified thickness ([e.g., 4mm or 5mm]). The work includes plasma or laser cutting of the plate to the approved architectural pattern/design, followed by a multi-stage finishing process: complete as per design given by project architect.				
		8.00	7575.00	Sqmt.	60600.00
45	Glass Elevation "Supply and installation of a Structural Glazing/Glass Facade system for the building elevation as per approved architectural designs. The system shall utilize [e.g., 6mm or 12mm] thick high-performance, heat-strengthened (reflective/low-e) of approved make (e.g., Saint Gobain, AIS). The glass shall be fixed to a structural framework of extruded aluminium sections (minimum alloy 6063 T5/T6) with a powder-coated finish (minimum 50-60 microns) or anodized finish (AC-15 grade). The assembly includes high-quality EPDM/neoprene gaskets, weather-grade silicone sealants for joint filling, and stainless steel (SS 304/316) anchor fasteners/brackets. The scope covers design, preparation of shop drawings, structural stability certificates, scaffolding, all lead and lifts, and final testing for water-tightness as per the satisfaction of the Engineer-in-Charge."				
		13.10	3535.00	Sqmt.	46308.50
46	LED SIGN BOARD FOR BUILDING Providing & Erecting Sign Board on Front of Building with base plate of 14 SWG GI Sheet. Using Acralic Sheet with Embose Letter upto 9" Height & appropriate width with osram make LED Watt Lighting in the letter with approved design by Engineer in Charge.(Incl. necessities White ACP (Aludecor) and MS Pipe Fabrication) (Incl. all type of labour and Material Charges etc.)				
		30.00	3060.30	Latter	91809.00

I. No.	Item Description	Qty.	Rate	Per	Amount
47	Stair Glass Railing "Supply and installation of architectural Glass Railing for staircases and landings as per approved designs. The system shall consist of [e.g., 12mm or 15mm] thick clear, heat-strengthened toughened safety glass with polished edges and rounded corners, conforming to IS 2553 (Part 1). The glass panels shall be supported by [e.g., SS 304/316 grade] stainless steel components, including top handrails (minimum 50mm dia, 2mm wall thickness), balusters/posts, or base-track profiles as per drawing. The assembly includes EPDM gaskets for glass cushioning, high-strength chemical anchor fasteners for floor mounting, and all necessary SS connectors/brackets. The scope includes preparation of shop drawings, all site measurements, scaffolding, cutting, welding/grinding of SS members, and final cleaning. The finished railing must be rigid, vibration-free, and meet all local safety codes for height and load-bearing capacity as directed by the Engineer-in-Charge.". (Vertical Three Steps Baluster) (MR)				
		22.00	8585.00	Rmt.	188870.00
48	Stair Steel Relling Providing and fixing 50x50mm And 19.5x19.5mm Stainless steel (S.S.304 Grade) Round pipe railing having thickness of 2.00mm and as directed by the engineer-in-charge including grinding, welding and polishing, etc. complete. (Vertical Three Steps Baluster) (MR)				
		11.30	4545.00	Rmt.	51358.50
49	Electric fitting : All the electrical work carried out consealed as per drawing given by consultant. All consealed pipe using polycab, wire using polycab / finolex, switch board moduler using GM/ VIHAN, Panel Board with main Switch using Schinder, Earthing with Chemical earth having 1.00 Mt earthing road. and all other acessories and materials using after approval by consultant. All the work carried out as per drawings and directed by consultant.(JOB)				
		1.00	303000.00	Job	303000.00
50	Fire Extinguisher : All the work carried out as per drawings and directed by consultant.				
	(A) ABC Type 6 K.G.				
		8.00	2525.00	No.	20200.00
	(B)CARBON DIOXIDE (CO2) TYPE EXTINGUISHER OF 4.5 KG.				
		8.00	3030.00	No.	24240.00
	(C) Modular Ceiling-Mounted Fire Extinguisher – MAP 50 – Refillable – 10kg				
		3.00	5050.00	Nos.	15150.00

I. No.	Item Description	Qty.	Rate	Per	Amount
51	Applying priming coat over new steel and other metal surface after and including preparing the surface by thoroughly cleaning, oil, grease, dirt and other foreign matter and scoured with brushes fine steel wood, scrapers and sand paper with ready mixed priming paint brushing red lead. (Pg No. 141/It Code 19001/It No. 19.2)				
		35.10	34.99	Sqmt.	1228.15
52	Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including cleaning the surface of all dirt, dust and other foreign matter. (Pg No. 141/It Code 19002/It No. 19.7)				
		35.10	92.20	Sqmt.	3236.22
53	Applying two coat soft putty & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.				
		566.60	75.75	Sqmt.	42919.95
54	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth. (Pg No. 140/It Code 18031/It No. 18.57)				
		566.60	82.85	Sqmt.	46942.81
55	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials. etc. complete (Pg No. 145/It Code 19031)				
		692.00	120.26	Sqmt.	83219.92

I. No.	Item Description	Qty.	Rate	Per	Amount
56	Stone clading "Providing and fixing of [e.g., 18mm to 30mm] thick natural Stone Cladding (Material: [e.g., Gwalior Mint Sandstone, Granite, or Travertine]) on vertical exterior/interior wall surfaces. The stone shall be of approved color, texture, and size [e.g., 600mm x 300mm]. For exterior high-rise applications, the stone must be fixed using a Mechanical Dry-Cladding system involving SS 304 grade anchor fasteners, Z-brackets, and pins to maintain a 15-20mm air gap. For interior/low-height applications, fixing may be done using high-polymer modified thin-set adhesive (conforming to IS 15477 Type 3). The work includes precise edge chamfering, groove cutting (as per architectural design), and application of a breathable, water-repellent silane-siloxane stone sealer. The rate includes all scaffolding, specialized labor for stone dressing, joint filling with non-staining weather-grade silicone sealant, and final cleaning. All work must be executed as per approved shop drawings and to the satisfaction of the Engineer-in-Charge."				
		10.80	5454.00	Sqmt.	58903.20
57	Supply, Installation, Testing & Commissioning of following size of Grid Tied Solar Power Plant with Solar Panels (ALMM approved): Frame Material : Anodized Aluminum alloy Frame With Twin Wall Profile, Front Cover : High Transmission Low-Iron Tempered Glass (AR Coated), High efficiency and positive power tolerance Pmax: 0/+5.				
	Module Efficiency should be approx. 18%-21%, Normal operating temperature 45°C, Junction Box with Waterproof IP67 & MC4 Compatible and Enclosed with Bypass diodes, 100% Electroluminescence test to ensure error free Modules, Thep. temp. co-efficient of the PV module shall equal or better than -0.45%/degree C. Solar PV modules of minimum fill factor 75% to be used. Unit Production:- 4 to 5 Unit /kw /day (Actual) (1Year Avg) With 10 year Product warranty and 25 year Linear Power Warranty.,				
	Solar Inverter: MPPT Range: 80-1000 V, Max efficiency: 97.5% - 98.9%, O/p Frequency: 50/60Hz, Operating Altitude (m) ≤4000, O/p Power Factor: ~1, O/P THDi: <3%, Operating Temperature Range: -25~60°C, Anti-islanding Protection:				

I. No.	Item Description	Qty.	Rate	Per	Amount
	Integrated, Input Reverse Polarity Protection Integrated, Insulation Resistor Detection Integrated, Residual Current Monitoring Unit Integrated, Output Over Current Protection Integrated, Output Short Circuit Protection Integrated,				
	Output Over Voltage Protection Integrated, Protection Degree: IP65, User Interface LCD & APP,Datalogger & Communication: GPRS / Wi-Fi, Module Mounting Structure: Seamless Box Pipe / 'C' Channel of suitable size for rooftop solar installations with good stability against wind & weight load., Hot Dipped Galvanized steel coils. suitable arrangement for base plate for foundation , solar panel mounting, the structure should be suitable for carry the load of solar panel,wiring, sprinkler system etc.				
	with necessary foundation work/ wall mount, j bolt, anchor fastner etc. the nut bolt used for installtion of stucture should be (SS 304) quality. and Balane of System with necessary Swithgears (Suitabel size and protection of ACDB & DCDB), inter connecting wiring, earthing system, lightining arrester system, all liasoning work with various gov. dipartment like state nodal agency, DISCOM & CEIG is included in agency scope				
	(Excluding GEDA Application fees, Solar connectivity Charges, Meter connectivity Charges, Meter testing Charges.)				
	Grid Tied Solar Power System: 7 - 10 kW (3 phase)				
		5.00	52016.01	KW	260080.05

I. No.	Item Description	Qty.	Rate	Per	Amount
58	Exhaust Fan "Providing , Installation, Testing, and Commissioning (SITC) of high-efficiency, axial/centrifugal exhaust fan of approved make (e.g., Almonard, Crompton, Havells) and specified sweep size [e.g., 300mm/450mm]. The unit shall feature aerodynamically contoured blades for maximum air delivery with minimum power consumption. The motor must be a totally enclosed, continuously rated heavy-duty type with a pressure die-cast aluminium rotor, mounted on double ball bearings for silent operation. The fixture shall have a degree of protection against dust and water entry of at least IP55. The frame and blades shall be treated with epoxy powder coating for superior corrosion resistance. The scope includes all necessary mounting accessories (MS brackets/frames), hardware (SS nuts, bolts), gravity louvers or bird screens, and internal wiring from the nearest point using FRLS copper cables. Work must include making good any wall openings and be completed to the satisfaction of the Engineer-in-Charge."				
		3.00	2525.00	No.	7575.00
59	Flower Pots "Supply and placement of premium architectural-grade flower pots/planters of specified size [e.g., 150mm Dia To 600mm] and approved design/shape (Circular/Rectangular/Tapered). The planters shall be fabricated from [specify material: High-Density Fiber-Reinforced Plastic (FRP) / GFRC Concrete / UV-Stabilized Polymer]. The finish shall be of approved shade with an exterior-grade, weather-resistant PU (Polyurethane) coating or natural stone texture. The pots must include integrated drainage holes with a filter layer (geotextile fabric) at the base to prevent soil leakage. The scope includes delivery to the site, placement at designated levels/locations as per the landscape plan, and providing necessary drainage trays or concealed internal stands where required. All units must be structurally sound, crack-resistant, and UV-stabilized to prevent fading under direct sunlight. Work to be completed to the satisfaction of the Engineer-in-Charge."				
		10.00	3030.00	No.	30300.00

I. No.	Item Description	Qty.	Rate	Per	Amount
60	Decorative Accessories "Supply, procurement, and installation of various architectural and interior decorative accessories as detailed in the Bill of Quantities (BOQ), interior design drawings, and approved sample boards/catalogs. The scope includes but is not limited to: wall art, framed prints, sculptural elements, high-end vases/planters, decorative mirrors, and bespoke artifacts. All items must be of premium quality, suitable for commercial/high-traffic use, and conform to the specified materials (e.g., polished stainless steel, hand-blown glass, reclaimed wood, high-grade ceramic). The item covers all necessary structural fixing arrangements, specialized mounting hardware (concealed brackets, security fittings), unpacking, careful handling, placement, and final aesthetic arrangement as directed by the Interior Designer/Architect/Engineer-in-Charge. All items must be delivered in pristine condition and carry a manufacturer's warranty of minimum 1 year against defects."				
		30.00	3030.00	No.	90900.00
61	Indoor Plants "Supply and installation of premium-grade, highly realistic artificial indoor plants and trees of specified species and dimensions as per the interior design schedule and approved samples. The item includes the plants (e.g., artificial Ficus Benjamina, Dracaena, custom green walls/moss frames), suitable growing medium substitute (e.g., faux soil/pebbles/decorative bark chips), and internal weighting for stability. All foliage shall be manufactured from high-quality, durable silk, plastic (PE/PVC), or UV-resistant fabric with naturalistic coloration, designed to replicate botanical accuracy. All material must be inherently fire-retardant (FR rated, conforming to NFPA 701 or equivalent standards) and certified as non-toxic. The scope includes placement within approved decorative planters (itemized separately), final aesthetic arrangement, and a minimum 2-year warranty against fading or material degradation. All work is to be executed to the satisfaction of the Interior Designer/Architect/Engineer-in-Charge."				
		10.00	3030.00	No.	30300.00

I. No.	Item Description	Qty.	Rate	Per	Amount
62	Notice Board "Supply and installation of a [e.g., 900mm x 1200mm] professional-grade enclosed notice board/display case. The board shall feature a robust extruded aluminium frame with a natural anodized or powder-coated finish ([e.g., matte silver or black]), fitted with a lockable, clear polycarbonate/acrylic hinged door (minimum 3mm thick) and high-quality cylinder lock and key set (two keys provided). The internal display surface shall be [specify: cork, felt fabric in approved color, or magnetic whiteboard surface] suitable for pushpins or magnets. The item includes all necessary mounting hardware (concealed brackets, heavy-duty screws/fasteners), scaffolding for high installations, and final commissioning/cleaning. The scope covers the supply of the board and installation to the satisfaction of the Engineer-in-Charge."				
		3.00	5050.00	No.	15150.00
63	Canvas Printed Painting Supplying and professionally installing high-resolution, archival-quality canvas printed paintings as detailed in the design schedule and approved samples is required.(Size 600 X 900 mm) The scope includes printing on a minimum 380 GSM poly-cotton canvas using fade-resistant UV-curable or pigment-based archival inks with a protective coating to prevent fading and allow for easy cleaning. The canvas shall be expertly gallery-wrapped over a warp-resistant, kiln-dried seasoned wooden stretcher frame (minimum 30mm thickness), with an optional decorative floating frame as specified. The rate covers all materials, robust heavy-duty SS hanging hardware, transport to site, careful handling, and final professional alignment/installation in Gujarat to the satisfaction of the Engineer-in-Charge,				
		4.00	2525.00	No.	10100.00

I. No.	Item Description	Qty.	Rate	Per	Amount
64	Providing and supplying G.I. wardrobe Door with two openable shutters, fabricated from Galvanized Iron sheet of approved make, with the body and shutters made out of minimum 20 Gauge thick sheet and frame/base made out of minimum 18 Gauge thick sheet, machine pressed, folded and properly reinforced wherever required. The wardrobe shall be provided with three hinged shutters fitted with heavy duty hinges, full length handle and three way locking arrangement with locking system and keys. All joints shall be continuously welded, ground smooth and finished properly. The entire unit shall be treated with anti-rust treatment including cleaning, degreasing and phosphating. The wardrobe shall be finished with electrostatic powder coating of approved make and selected colour, with oven baked finish for durability. The item shall include all accessories such as handles, hinges, locks, stoppers, supports, hardware etc. complete in all respects.				
		9.90	5050.00	No.	49995.00
Total Amount Rs..					6434991.95
Roundup Amount Rs..					6434992.00

NOTE: Rate given in Price schedule are excluding GST. Contractor shall have quote the tender without GST. GST will be paid extra by AJPSSSM-AMRELI

Stamp with Signature of Contractor

Cons. Engineer
Neha Consultancy

Manager
AJPSSSM-AMRELI

Chairman
AJPSSSM-AMRELI